

<b>Operation</b>	<b>Tool string</b>	<b>Depth (m WRF/LRF)</b>	<b>Depth (m WSF/LSF)</b>	<b>Deployment</b>
Jet-in 36" conductor pipe		~2135.6	~54.5	
Riserless 25" drilling, Leak-off test	MWD/APWD/GR	2135.6~2793.8	54.5~712.7	1A
Leak-off test		2784.8~2796.8	703.7~715.7	
Riser drilling (12-1/4" bit)	MWD/GR	2793.8~3590.8	712.7~1509.7	1B
Riser drilling and coring	MWD/GR	3590.8~3674	1509.7~1593.9	1C
Hole opening to 12-1/4"	MWD/GR	~3684.8	~1603.7	1D
Wireline logging Run 1 (Main)	EMS/HRLA/PEX/GR	2773.4~3670.2	692.3~1589.1	2
Wireline logging Run 1 (Repeat)	EMS/HRLA/PEX/GR	3570.6~3662.2	1489.5~1590.4	
Wireline logging Run 2 (Main)	FMI/HNGC/SonicScanner/EMS/PPC	2755.8~3662.2	674.7~1581.1	3
Wireline logging Run 2 (Repeat)	FMI/HNGC/SonicScanner/EMS/PPC	2844.8~2901	763.7~818.9	
Wireline logging Run 3	MDT/GR	14 stations		4
Hole opening to 17"	MWD/GR	2799~3650	717.9~1568.9	5
Wireline logging Run 4	Junk basket (8-1/4" gauge ring)	0~3300	0~1218.9	
Wireline logging Run 5 )	VSI-16 (WVSP, CVSP and ZOVSP)	0~3217.8	0~1136.7	6

Table 1.Site C0009A summary of drilling and coring operations.